

Specification
of Mason Work to be done
in erecting a Police Station
at Dorchester. —

Wm. B. Mayhew

Specification of Mason work to be done in erecting a Police Station at Dornoch conform to accompanying drawings. —

The Contractor is to remove the dyke in front of the site and to use the stones in the foundations so far as they will go and can be made available for the purpose, and he is to furnish all other materials Carriages and workmanship. —

The site is to the Eastward of the Prison — on the East side of the River, and the North front of the Station is to be on a line with the North front of the Prison. — The finished surface of the ground in front of the entrance door to be on a level with the Centre of the road immediately opposite to it, and the ground floor to be 18 inches above this level. The tracks for walls to be cut ^{or deeper if necessary} to the depth of 18 inches below the natural surface of the lowest part of the site, ^{as in the printed one} the black earth may be laid in heaps in the yard or disposed of ^{as in the printed one} the other excavations and rubbish that may accumulate to be used in making up the Area under the pavement, and any over-plus of rubbish to be removed. —

The stones to be taken from Dornoch quarry and to be of the best that the quarry will produce. —

Rubble Work. —

The foundations to be laid with large flat bedded stones to form scarcements of 4 inches projection outside, and 4 inches inside where the floors are paved; and 6 inches where the floors are of wood, — and the brick scarcements to be carried up and levelled for the sleepers to rest on. — All the walls to be carried up to the dimensions figured on the drawings — and excepting the parts of the external faces afterwards specified — to be built of good rubble work with Hammer dressed stones laid on their natural and broadest beds, the outer faces of all the walls — excepting the North front to be square pick dressed ashlar laid in level courses averaging 7 inches high on face — 12 two courses of ashlar to every course of rebate and corners,

1/2 being 9 inches
on the outside
less than the
level of Prison
entrance gate

or deeper if necessary
to be removed
all rubbish must